Bruhath Bangalore Mahanagara Palike Dasarahalli Zone

PROJECT SUB-DIVISION-01

Name of Work: Modified Estimate for Providing Safety Grill work over the Existing Boundary fencing at Abbigere Park, in Ward no. 12

Est .Cost Rs. 20.00 Lakhs

Sl No	Description of Items	Unit	No	L	B	D	Qty	Rate	Amount
1	Providing & fixing M.S. Grill over existing compound wall as per Chief Architect drawing No.12686, using 16mmx16mm M.S. Square rod at 150mm c/c spacing and 6mmx40mm M.S flats at horizontal and 6mm x12mm M.S. flat for ornamental design and providing shop edge design at the vertex of every vertical rods, including welding, grinding wherever necessary. All the steel surface should be thoroughly cleaned free of rust and painted with anti corrosive paint (shop paint) etc., complete. The work includes cost of all materials, labour charges for all items of work, hire charges for welding, cutting and grinding equipment, and electricity charges, etc., complete as per specification Page No. 47/ Item No. 7.36/ PWD SR 2014-15								
	over the Existing Boundary fencing		4	125.40		0.60	300.96		
							300.96	5982.64	1800535.00
	Basic Rate	5,644.00							
	Area Weightage @ 6%	338.64							
	Total	5,982.64							
									1800535.00
2	Add: 10% KRIDL Charges + Cess 1%								198058.85
3	Miscellaneous and unforseen Charges								1406
								Total	2000000.00
	(Rupees Twenty Lakhs Only)								

CERTIFICATE

1 The Work spot has been inspected and the work found to be necessary
2 The Estimate is prepared as per the PWD SR 2014-15
3 The Provision made in estimate are adequate and essential
4 This area comes under BBMP limits.

Ravi M.K.
Asst Engineer
Project Sub-Division

Asst Executive Engineer
Project Sub-Division
Dasarahalli Zone, BBMP

Executive Engineer
Dasarahalli Zone
BBMP

CE/DZ/TS/80/14-15
ನಂ. Pg 77 ದಿನಾಂಕ : 04/12/2014
ರೂ. 20,00,000/- (ಸುಮಾರು ಇಪ್ಪತ್ತು ಲಕ್ಷ)
ಗಳ ಅಭಿವೃದ್ಧಿ ಪಟ್ಟಿಗೆ ತಾಂತ್ರಿಕ ಮಂಜೂರಾತಿ ನೀಡಿದೆ.
ಮುಖ್ಯ ಅಭಿಯಂತರರು
ತಾಂತ್ರಿಕ ಸಹಾಯಕರು ಬಿ.ಬಿ.ಎಂ.ಪಿ.
ದಾಸರಹಳ್ಳಿ ವಲಯ, ಬೆಂಗಳೂರು.

Job code No 012-13-000218.
P code - 0190.